

KUBISCHE BERECHNUNG (SIA 116)

						Untergeschoss	Halle Werkstatt	Verwaltung
Geschoss	Länge	Breite	Fläche	Höhe	Zuschlag			
Untergeschoss						12'238		-
1	Einstellhalle	54.26	24.26	1'316.35	4.53	5'963		
2	Einstellhalle	54.26	13.86	752.04	5.43	4'084		
3	Teilrampe	11.07	5.50	60.89	5.43	331		
4	Disponibel	11.07	10.37	114.80	5.43	623		
5	Disponibel	11.07	5.94	65.76	4.53	298		
6	Disponibel	9.07	13.64	123.71	4.53	560		
7	Rampe Rest			151.80	2.50	380		
Erdgeschoss							10'370	1'957
1	Werkstatt Süd	42.53	13.68	568.81	10.34	5'881		
2	Werkstatt Nord	12.44	10.72	133.36	10.67	1'423		
3	Werkstatt Nord	23.41	10.72	250.96	4.86	1'220		
4	Teillager	6.22	10.72	79.68	4.86	387		
5	Teillager / Gang	5.50	7.24	39.82	4.86	194		
6	Lift	2.70	3.48	9.40	3.42	32		
7	Treppe	2.80	3.48	9.74	3.42			33
8	Fahrzeugübergabe	7.26	9.22	66.94	6.30			422
9	Fahrzeugübergabe	9.05	6.28	56.83	7.50	FDZ, +1.00		426
10	Shop / Büros	5.04	12.05	60.73	3.42			208
11	Ausst., Büros	16.31	13.55	221.00	3.42			756
12	Verkauf / Büro	2.00	6.43	12.86	3.42			44
13	Büro	12.27	1.63	20.00	3.42			68
14	Vordach Werkstatt	54.80	15.00	822.00	1.5	FDZ, +1.00		1'233
Obergeschoss							1'916	2'654
1	Schreinerei / Lager	23.51	10.72	252.03	5.80	1'462		
2	Lager	11.72	7.04	82.51	5.50	454		
3	Garderobe / Treppe	11.72	5.62	65.87	2.88			190
4	Shop / Luftraum	7.26	3.44	24.97	2.88			72
5	Shop	9.05	3.44	31.13	4.08	FDZ, +1.00		127
6	Aufenthalt / Büro	12.50	11.74	146.75	2.88			423
7	Bespr. / Büro	9.05	10.10	91.41	4.08	FDZ, +1.00		373
8	Verkauf / Büro	2.00	6.42	12.84	4.08	FDZ, +1.00		52
9	Vordach			57.10	1.50			86
Dachgeschoss							-	1'332
1	Garderobe / WC	6.02	5.62	33.83	5.05	bis Dach, + DZ		171
2	Lift	2.90	3.18	9.22	5.56	FDZ, +1.00		51
3	Treppenhaus	2.90	2.44	7.08	5.05	bis Dach, + DZ		36
4	Treppenhaus	2.60	5.62	14.61	3.90	bis Dach, + DZ		57
5	Kantine / Estrich	7.46	24.40	182.02	4.19	bis Dach, + DZ		763
6	Estrich / Lager	5.04	11.74	59.17	3.51	bis Dach, + DZ		208
7	Vordach Terrasse	4.00	7.72	30.88	1.50	FDZ, +1.00		46
Aufrundung (Stützmauern, Aussentreppe)						12'238	12'286	5'942
						62	14	58
TOTAL RAUMINHALT UNTERGESCHOSS						m3	12'300	
TOTAL RAUMINHALT WERKSTATTHALLE						m3	12'300	
TOTAL RAUMINHALT BÜROBEREICH						m3		6'000

Total

30'600